

Recuperação de Linha de Transmissão de Energia Mocuba (Província da Zambézia), Moçambique **Restoration of 220 kV Transmission Line Section** *Mocuba (Zambezia Province), Mozambique*

Work Description

The Seth awarded the work of emergency restore power infrastructures damaged by floods in Mocuba (Zambezia Province).

Due the heavy floods that struck the central and northern region of Mozambique in January 2015, the Centre-Northern 220 KV Transmission Line running from Matambo Station, in Tete up to Nampula substation, in Nampula, became unavailable for 27 days after ten (10) of its Self Supportive steel Towers were devastated by waters of Licungo river on its Line crossing point at Mocuba District, in Zambezia Province.

The summary of the scope of the project was consist of supplying eleven new towers, power and earth conductors, insulators, fittings, earthing systems, as well as installation.

It was also part of the contract the execution of the respective towers foundations.



Resumo da Obra **Work Summary**

Cliente	EDM – Electricidade de Moçambique	<i>Client</i>
Tipo de contrato	Série de Preços Measurable	<i>Contract type</i>
Data de construção	2015	<i>Construction period</i>
Custo	EUR 3.415.377,00	<i>Cost</i>