

Dragagens nos Estaleiros Navais de Porto Amboim

Porto Amboim, Angola

*Dredging works in the basin of PAENAL shipyard
Porto Amboim, Angola*

Descrição dos Trabalhos

Dragagem de 650.000 m³ de areia da bacia do cais com draga de sucção "GEFION R" da Rhode Nielsen.

Remoção de 1.300 m de pipelines e diversas estruturas (maciços de betão, âncoras, cabos de aço, destroços diversos) enterradas no leito da bacia com embarcação tipo Multicat auxiliado por bomba de dragagem de areia "DOP" e equipa de mergulhadores.

Números mais significativos:

650.000,00 m³ de dragagens

Meios especiais utilizados:

Draga de arrasto e sucção "GEFION R" da R&N
Bomba de dragagem de areia DOP
Embarcação multicat "JIFWORKER" da Jifmar



Dredging with DOP pump

The scope of work included:

Dredging of one basin with a Rhode Nielsen (R&N) trailing hopper suction dredger (650,000.00 m³).

Removal of sundry equipment buried in the sea bed (pipelines, concrete blocks, anchors, steel cables). This work was made with a vessel type Multicat aided by a dredge pump "DOP" and a diving team.

Most significant figures:

650,000.00 m³ of dredging

Special Means:

Trailing hopper suction dredge "Gefion R"
Dredge pump type DOP
Vessel type Multicat



Draga de arrasto e sucção na bacia do cais dos estaleiros navais de Porto Amboim
Trailing hopper suction dredger in the dock of PAENAL shipyard of Porto Amboim

Resumo da Obra

Work Summary

Cliente	PAENAL	<i>Client</i>
Tipo de contrato	Porto Amboim Estaleiros Navais, Lda Preço global <i>Lump sum</i>	<i>Contract type</i>
Data de construção	2013	<i>Construction period</i>
Custo	9.228.265,19 USD	<i>Cost</i>

