

Dragagens nos Estaleiros Navais de Porto Amboim

Porto Amboim, Angola

Works of dredging in the basin of PAENAL shipyards

Porto Amboim, Angola

Descrição dos trabalhos

O âmbito dos trabalhos incluiu:

Dragagem de 650.000 m³ de areia da bacia do cais com draga de sucção "GEFION R" da Rhode Nielsen
Remoção de 1.300 m de *pipelines* e diversas estruturas (maciços de betão, âncoras, cabos de aço, destroços, etc...) enterradas no leito da bacia com embarcação alugada tipo Multicat auxiliado por bomba de dragagem de areia "DOP" e equipa de mergulhadores.

Números mais significativos:

650.000,00 m³ de dragagens

Meios especiais utilizados:

Draga de sucção "GEFION R" da Rhode Nielsen
Bomba de dragagem de areia DOP
Embarcação multical "JIFWORKER" da Jifmar



Zona das dragagens durante os trabalhos
Zone of dredging during the works

Work Description

The scope of work included:

Dredging of one basin with a Rhode Nielsen suction dredger (650,000.00 m³).

Removal of sundry equipment buried in the sea bed (as pipelines (1.300 m long) concrete blocks, anchors, steel cables).

This work was made with a rented vessel type Multical aided pump dredging "DOP" and divers team.

Most significant figures:

650,000.00 m³ of dredging

Special Means:

Suction dredge Rhode Nielsen
Pump dredging type DOP
Vessel type Multical



Draga de sucção na bacia do cais dos estaleiros navais de Porto Amboim
Suction dredger in the dock of shipyards of Porto Amboim

Resumo da Obra

Work Summary

Cliente	PAENAL	<i>Client</i>
Tipo de contrato	Porto Amboim Estaleiros Navais, Lda Preço global <i>Lump sum</i>	<i>Contract type</i>
Data de construção	2013	<i>Construction period</i>
Custo	9,228,265.19 USD	<i>Cost</i>